

Estimate of Remedial Cost
Connecticut Department of Transportation Westbrook Maintenance Facility
201 Horse Hill Road (Route 145)
Westbrook, Connecticut

ALTERNATIVE 1 - EXCAVATION & OFF-SITE DISPOSAL

Description: This alternative includes the excavation and off site disposal of all contaminated material in AOC #5 - Fill Area, regrading the area, installation of 3 monitor wells and long term groundwater monitoring (4 years) of the area. Also included is the cleaning and disposal of sludge/sediment from the floor drains, piping and floor drain cleanout. One additional round of groundwater monitoring of the existing wells at the Site is also included.

Item Description	Quantity	Units	Unit Price	Costs
Solid Waste Disruption Authorization	1	LS	\$ 3,300.00	\$ 3,300.00
Remedial Action Plan	1	LS	\$ 6,600.00	\$ 6,600.00
Excavation	500	CY	\$ 18.00	\$ 9,000.00
Transportation & Disposal	800	TON	\$ 50.00	\$ 40,000.00
Bulky Waste Disposal	1	LS	\$ 1,000.00	\$ 1,000.00
Monitor Well Installation	3	EACH	\$ 750.00	\$ 2,250.00
Post-remediation monitoring	16	QTR	\$ 3,700.00	\$ 59,200.00
Floor Drain Cleaning, Material Disposal & Closure	1	LS	\$ 5,000.00	\$ 5,000.00
One Round GW Monitoring of Existing Wells	1	EACH	\$ 3,300.00	\$ 3,300.00
Environmental Condition Assessment Form Filing	1	LS	\$ 6,600.00	\$ 6,600.00
Establish Environmental Land Use Restriction	1	LS	\$ 6,600.00	\$ 6,600.00
Closure Report and LEP Verification	1	LS	\$ 3,300.00	\$ 3,300.00
Total				\$ 146,150.00